

BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Name of Work: Estimate for Providing Water Supply through Drilling new Borewells and Water Pipe line in Hebbala, Kariyanna Layout, Errannapalya, Kempapura, Mariyannapalya, Amruthahalli and Surrounding areas in Ward No. 07, Byatarayanapura.

007-18-000013		P-3293 14th Finance					Est Cost Rs.	9900000.00	
SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging technical personal and labour required etc., as per Specification and direction (P.48, I. 9.4) PRED.SR 2012-13	Each BW							
			12				12	1938.46	23262.00
2	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.) P. 46 / I. 9.1 PRED SR 2012-13	Rmtr							
			12	50.00			600.00	315.18	189108.00
	0 to 50 m		12	50.00			600.00	412.00	247200.00
	50 to 100 m		12	50.00			600.00	458.35	275010.00
	100 to 150 m		12	50.00			600.00	484.10	290460.00
	150 to 200 m		12	50.00			600.00	560.32	336192.00
	200 to 250 m		12	50.00			600.00	600.49	360294.00
	250 to 300 m								
3	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty P. iii, I No. 84 PRED SR 2012-13	Rmtr							
			12	70.00			840.00	1325.00	1113000.00

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
4	Providing 250mm dia PVC Pipe 6kg/cm BWSSB SR 2014-15 Page No. 53, Item No. 1(ii)	Rmtr	12	18.00			216.00	1100.00	237600.00
5	Providing and fixing 160mm Borewell Cap P. iii, I No. 85 PRED SR 2012-13	Each	12				12	100.00	1200.00
6	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for operation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required accessories such as suction, casing suction strainers sand guard Non return value etc. complete. The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps PWD SR 2016-17 P. XXXXII Item No. 21 including of all taxes	No	12				12	50100.00	601200.00
7	10 HP 20 Stage KSRB13-3.6 : Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.6 Page No. 89, Item No. 13.15 PWD SR 2016-17	m	12	280.00			3360.00	457.92	1538611.00
	Basic Rate		432.00						
	Area Weightage @ 6%		25.92						
	Total		457.92						
8	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 4 Sqm mm KPWD Electrical SR 2014-15	Mtr	12x2	290.00			6960.00	126.70	881832.00
9	Labour charges for erection as new /repaired submercible pumpset along with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset should be handed over to department including transportation (Each lenth =6.00) Page No. 558, Items No-3 BWSSB SR for 2014-15)	Per Length	12	49.00			588	88.00	51744.00

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
10	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15	Each	12				12	302.00	3624.00
11	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15	Mtr	12	35.00			420.00	140.40	58968.00
12	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required. In existing trench/duct. P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15	Mtr	12	35.00			420.00	10.80	4536.00
13	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete. (As per Civil SR KSRB I-2, P-7) P No. 61 / I No. 7.9.3 KPWD Electrical SR 2014-15	Mtr	12	30.00			360.00	85.00	30600.00
	For Cutting Road Surface		12	30.00					
14	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV P No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15	Mtr	12	4.00			48.00	345.00	16560.00
	40mm dia GI pipe		12	4.00					
15	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P No. 62 / I No. 7.13.2 KPWD Electrical SR 2014-15	No.	12				12.00	280.00	3360.00
	16Sqmm		12						
16	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, (P No. 55, I No. 7.1) KPWD Electrical SR 2014-15	No	12				12	2727.00	32724.00

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
17	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15	No.							
	32 Amps		12x6	✓			72	180.00	12960.00
18	KSRB13-7.1-4 : Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.10 / 13.13 Page No. 93, Item No. 13.55, PWD SR 2016-17	Nos							
			12				12	1585.76	19029.00
	Basic Rate	1496.00	✓						
	Area Weightage @ 6%	89.76	✓						
	Total	1585.76	✓						
19	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.- for 50mm dia: Page No. 95 , Item No. 13.81.3 PWD SR 2016-17	Each							
	50mm dia		12				12	227.90	2735.00
	Basic Rate	215.00	✓						
	Area Weightage @ 6%	12.90	✓						
	Total	227.90	✓						
20	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete P. XXXVII PWD SR 2016-17	No							
			12	4.00			48	104.30	5006.00
21	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps Group A TPN P No. 47 / I No.6.16.5 KPWD SR 2014-15	No		✓	✓				
			12				12	1547.00	18564.00
22	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete P.No. 57, I. No. 6.41.2 KPWD Electrical SR 2014-15	Sq.Cm		✓					
	16SWG		12x2	120.00	60.00		172800.00		
			12	360.00	25.00		108000.00		
							280800.00	0.33	92664.00

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
23	Supplying fully automatic store delta starter unit push button type with suitable wires three contractors one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts 3phase and wired offter fixing to the wooden board for motor upto 12.50 HP (KPWD electrical SR for 2014-15 Page No. 44 Item No. 6.2.1)	No.	12				12	6583.00	78996.00
25	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including sharing and strutting danger lighting and using site rails and boring poles at every 100 mtrs wherever necessary as directed in th following structure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil	Cum	12	70.00	0.60	0.60	302.40		
	For CPVC Pipe		1	280.00	0.60	0.60	100.80		
			1	300.00	0.60	0.60	108.00		
			1	250.00	0.60	0.60	90.00		
			1	100.00	0.60	0.60	36.00		
							637.20	188.00	119794.00
	Basic Rate	188.00							
26	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and includng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13.	Rmtr	12	70.00			840.00		
	75 mm dia 6 KSC PVC pipe						840.00	157.00	131880.00
	Basic Rate	157.00							
27	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 50mm nominal OD pipes. (P.No. 96 / I. No. 13.85.6 of PWD SR 2016-17)	m	1	280.00			280.00		
	For Pipeline		1	300.00			300.00		
			1	250.00			250.00		
			1	100.00			100.00		
							930.00	475.20	441936.00
	Basic Rate	440.00							
	Area Weightage @ 8%	35.20							
	Total	475.20							
28	KSRRB M1200-46. Sand filling in wells complete as per drawing and technical specifications MORTH Specification No.1207 Page No. 213, Page No. 26.124, PWD SR 2016-17	Cum							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
			12	70.00	0.60	0.30	151.20		
			1	280.00	0.60	0.30	50.40		
			1	300.00	0.60	0.30	54.00		
			1	250.00	0.60	0.30	45.00		
			1	100.00	0.60	0.30	18.00		
							318.60	2922.42	931083.00
	Basic Rate	2757.00							
	Area Weightage @ 6%	165.42							
	Total	2922.42							
29	Refilling the basement and pipeline trenches with selected available earth for trench excavation including authority condition in layers from the di including dispensary of the surplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13	Cum							
							Qty. Vide Item No. 25-27	318.60	61.00
	Basic Rate	61.00							
30	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation , including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. Page No.12, Item No. 4.3 of PWD SR 2016-17	Cum							
			1	84.00	0.60	0.15	7.56		
			1	90.00	0.60	0.15	8.10		
			1	75.00	0.60	0.15	6.75		
			1	30.00	0.60	0.15	2.70		
							25.11	5256.36	131987.00
	Basic Rate	4867.00							
	Area Weightage @ 8%	389.36							
	Total	5256.36							
31	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 18, Item No. 4.48, PWD SR 2016-17	Cum							
			1	84.00	0.60	0.15	7.56		
			1	90.00	0.60	0.15	8.10		
			1	75.00	0.60	0.15	6.75		
			1	30.00	0.60	0.15	2.70		
							25.11	6349.32	159431.00
	Basic Rate	5879.00							
	Area Weightage @ 8%	470.32							
	Total	6349.32							

SI No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
32	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 Page No. 158 / Item No. 20.18, PWD SR 2016-17	Cum							
			1	196.00	0.60	0.20	23.52		
			1	210.00	0.60	0.15	18.90		
			1	140.00	0.60	0.15	12.60		
			1	70.00	0.60	0.15	6.30		
							61.32	1768.08	108419.00
	Basic Rate	1668.00							
	Area Weightage @ 6%	100.08							
	Total	1768.08							
33	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502 Page No. 161 / Item No. 21.6, PWD SR 2016-17	Sqm							
			1	196.00	0.60		117.60		
			1	210.00	0.60		126.00		
			1	140.00	0.60		84.00		
			1	70.00	0.60		42.00		
							369.60	27.56	10186.00
	Basic Rate	26.00							
	Area Weightage @ 6%	1.56							
	Total	27.56							
34	KSRRB M500-19. Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509 - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % VG-30 Bitumen Page No. 165 / Item No. 21.22.6, PWD SR 2016-17	Cum							
			1	196.00	0.60	0.040	4.70		
			1	210.00	0.60	0.040	5.04		
			1	140.00	0.60	0.040	3.36		
			1	70.00	0.60	0.040	1.68		
							14.78	7083.98	104730.00
	Basic Rate	6683.00							
	Area Weightage @ 6%	400.98							
	Total	7083.98							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
35	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. P. No.92 / I. No. 13.38 PWD SR 2016-17	Each							
			35				35	2781.00	97335.00
	Basic Rate	2575.00							
	Area Weightage @ 8%	206.00							
	Total	2781.00							
	Sub Total								8783255.00
	KRIDL Charges @ 10%								878326.00
	Labour Cess @ 1%								87833.00
	Borewell BESCOM Deposit		12	12500.00					150000.00
	Miscellaneous and Unforeseen Charges	L/S							586.00
								Total	9900000.00
Rupees Ninety Nine Lakh(s) Only									

CERTIFICATE:

- 1 The work spot has been inspected and the work is found necessary.
- 2 This estimate is prepared as per C.S.R. of PWD 2016-17, PWD Electrical 2014-15, PRED 2012-13 & approved Rate.
- 3 The provisions were made in this estimate are necessary and adequate.
- 4 This works come under B.B.M.P. limits.

M. H. U. N. D.
Assistant Engineer
Ward No. 07

Devi
Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Kodigehalli Sub Division

M. Chandra Sekhara 22/12
Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Sub Division
Shree 22/12

ADMINISTRATIVE APPROVAL	
Accorded For Rs.	<i>Ninety Nine lakhs only</i>
Head of A/c.	<i>P - 3297</i>
Div. Ref. No.	<i>129/17-18</i>
Date.	<i>22/12/17</i>
<i>Shree</i> 22/12 AE	<i>M. Chandra Sekhara</i> 22/12 EE(BTP)

Technical Sanction
Accorded For *99.00 lakh Rs.*
Head of A/C. *P 3293*
CER NO : *497* Dt: *27/12/17*
TA *CE (YNK)*